

Addendum #1

Tender to Screen, Crush, Stockpile and Haul Granular Materials at Township Locations  
Tender No. T-01-2017

**Please Note the tender closing has been extended to  
Friday, May 19, 2017 12:00 p.m.**

**Part "C" Specifications**  
**Basis of Payment**

Payment at the contract unit price shall be per metric tonne of granular produced and stockpiled.

The contractor shall use belt/conveyor scales for the making of all products to ensure the desired quantity is achieved. *The quantities of sand cannot be specified as it is a by-product for the quantities of 5/8 gravel. The Township will still need to know the quantity of sand after screening.* The Township may verify the final quantity by cross section measurements.

**Part "D" Bid Form**  
**Schedule of Items & Pricing**

<b>Tender Summary</b>			
Screen, Crush and Stockpile at Edwards Pit, 1450 County Road 4, Warsaw, ON. All material from the bank will be screened <i>prior to</i> crushing to remove sand from the stone aggregate and the stone aggregate will be crushed to make 5/8 Gravel. The 2 inch material can be crushed from the bank to make the quantity. The contractor will provide a breaker to crush oversized material.			
<i>Screening Sand</i>	\$_____ per tonne		
	<b>Tonnes</b>	<b>Unit Rate</b>	<b>Amount</b>
Crush and Stockpile 5/8 Gravel at Edwards Pit	43,000	\$	\$
Crush and Stockpile 2 inch Gravel at Edwards Pit	23,000	\$	\$
Subtotal			\$
H.S.T.			\$
Total Tendered Price Complete			\$

<b>Load, Haul and Place</b>		
Load, haul and place material from Edwards Pit to location		
	<b>Tonnes</b>	<b>Trucking Cost</b>
Load, haul and place 6,241 tonnes of 5/8 crushed Limestone from Edwards Pit to Eighth Line Road South Dummer from Webster Road to North Limit at a mutually agreed date and time	6,241	\$
Load, haul and place 3467 tonnes of 5/8 crushed Limestone from Edwards Pit to Eighth Line Road South Dummer from County Road 8 to Webster Road at a mutually agreed date and time	3,467	\$
Load, haul and place 2601 tonnes of 5/8 crushed Limestone from Edwards Pit to Third Line Road Dummer from Caves Road to County Road 6 at a mutually agreed date and time	2,601	\$
Load, haul and place 3,467 tonnes of 5/8 crushed Limestone from Edwards Pit to Clifford Road from Third Line Road South Dummer to South Street at a mutually agreed date and time	3,467	\$
Subtotal		\$
H.S.T.		\$
Total Trucking Costs		\$